

NORTHQUEST LTD
ABANDONMENT AND RESTORATION PLAN
PISTOL BAY PROJECT, NUNAVUT

Prepared by: Dwayne Car
Revision 1: Stanley Robinson
Revision 2: Stanley Robinson
Revision 3: Stanley Robinson
Revision 4: David Smith
Revision 5: Stanley Robinson
Revision 6: Denise Lockett

May 2015
March 2017
November 2017
December 2018
June 2019
March 2020
October 2021

NORDGOLD (Northquest Ltd.)
Suite 301 - 82 Richmond Street East,
Toronto, Ontario
Canada M5C 1P1

www.nordgold.com

Table of Contents

	Page
1. Preamble - - - - -	3
2. Introduction - - - - -	4
3. Background Information on the Campsite - - - - -	4
4. Schedule - - - - -	4
5. Infrastructure - - - - -	5
6. Seasonal Shutdown - - - - -	6
7. Final Abandonment Plan - - - - -	7
8. Contact Numbers for Relevant Organizations - - - - -	8

1. Preamble

This Abandonment and Restoration Plan (A&R Plan) is in effect until the expiry of Northquest's water licence and land use permits and applies to the work areas planned for the Pistol Bay property. These work areas lie within the municipal boundary of Whale Cove, on Crown Land and on Kivalliq Inuit Association (KIA) Inuit Owned (IOL) surface land.

Northquest has received licences and permits from Crown Indigenous Relations and Northern Affairs Canada (CIRNAC) for exploration activities on Crown Land, the Kivalliq Inuit Association (KIA) for activities on Inuit Owned surface land (IOL), a water licence from the Nunavut Water Board (NWB) for water use and waste disposal related to the project, as well as permission from the Hamlet of Whale Cove and Permission to Occupy from the Government of Nunavut Department of Community and Government Services (GN CGS) for activities on Commissioners Land.

Questions or concerns regarding this Plan can be directed to

David Smith
Exploration Manager, Canada
NORDGOLD (Northquest Ltd.)
Suite 301 - 82 Richmond Street East,
Toronto, Ontario
Canada M5C 1P1

T: (416) 306-0954
C: (647) 549-0954
EMAIL: david.smith@nordgold.com
www.nordgold.com

2. Introduction

This Plan has been prepared for one temporary campsite and several proposed diamond drilling locations on Northquest Ltd's Pistol Bay project. The new campsite is located at Latitude: 62° 20' 30" Longitude: 92° 49' 48" W.

The old Pistol Bay camp has been in place since 2011 and is fully owned by Northquest Ltd. The camp consists of several aluminum framed 14' by 16' tents on plywood floors, a plywood kitchen, a plywood core logging tent, and can accommodate up to 35 people.

Exploration based out of the camp generally consists of prospecting, till sampling, geophysical surveys, mapping, and diamond drilling.

3. Background Information on the Campsite

The Pistol Bay camp has been in place since 2011 at Latitude: 62° 21 ' 05 " N Longitude: 92° 45 ' 20" W until it was moved to a new location, closer to the Vickers Deposit and the Hamlet of Whale Cove, at Latitude: 62° 20' 30" Longitude: 92° 49' 48" W in the 2022, and with a water source that does not freeze to the bottom in winter.

The new camp site location is approximately 4.2km west of the old site. The proposed new site is 300-400m northwest of and downslope from an old, abandoned trailer near the main road, approximately 22km from town. Water can be drawn from the fish-bearing lake approximately 550m northwest from the old, abandoned trailer.

The new camp site was selected because it is considerably closer to the Vickers Gold Deposit, and it will allow the company to operate year-round. Moving the camp is also more cost effective than building a new camp.

Northquest Ltd personnel and contractors can travel by pick-up to Whale Cove, the Whale Cove airport and to the Vickers drill target. However, a helicopter is still the primary mode of transport for the project.

The old camp site will be cleaned up and restored to its original condition.

4. Schedule

The effective date of the plan is June 25, 2015. The restoration of the camp will occur when the program has been completed and will be finished prior to expiration of the renewed water licence, unless another renewal is applied for. Each drill site will be restored as soon as the drill is moved to a new location (progressive reclamation).

5. Infrastructure

Structures:

- Thirteen x 14' x 16' Weatherhaven sleep tents heated with propane
- One 14 x 48' plywood kitchen heated with propane
- One 14' x 16' plywood shack heated with propane and used for sample shipment preparation and sample drying. Previously, this building was the core shed.
- One 16' x 24' plywood core shack, heated with fuel oil.
- One 14' x 16' Weatherhaven shower/laundry facility, heated with propane, with an 8' x 16' extension which houses the laundry facilities, water storage tanks, water heater and water treatment system
- One 14' x 16' Weatherhaven core cutting tent
- One 14' x 16' Weatherhaven storage tent
- One 14' x 20' Weatherhaven office tent heated with propane
- One 8' x 8' plywood equipment shack
- Three plywood outhouses
- One heli-pad made of plywood framed with wooden pallets
- Two fuel caches stored in four "Insta berms" equipped with water drains
- Spill response equipment located beside fuel berms and heli-pad
- Two plywood generator shacks 8' x 16'
- One 16' x 8' extension to plywood core logging shack
- One 8' x 8' shed to contain electrical panels
- One 16' x 16' plywood dry (heated by fuel oil)
- One plywood emergency shelter (used at drill rig)

Northquest Machinery (end of the 2021 field season):

- One 2013 Ford F250 ¾ ton pick-up Truck
- One 2014 TRX500FM Honda ATV
- One 2014 TRX420FE Honda ATV
- One 2011 TRX500 Honda ATV
- One 2016 TRX 500FM Honda ATV
- Two Honda 6500 generators
- One gas portable rock saw
- Two 33.1Kva generators (main power plant and spare for camp).
- Two 50 cc Honda water pumps
- One Smart Ash portable, multipurpose batch load incinerator
- One gas-powered hydraulic barrel crusher
- One Kubota M6060 tractor
- One Sure-track trailer model ST8214TLDD
- Two Vancon Core Saws, 3hp, electric

Top Rank Diamond Drilling Limited machinery on site at the end of the 2021 field season:

- Two Discovery 2 diamond drills, with 4 Perkins engines
- Three Honda generators
- One Yamaha generators
- One generic generator
- One Lincoln welder
- One Miller welder
- Seven Water pumps
- Four Honda 2" water pumps

6. Seasonal Shutdowns

Buildings and Contents

All doors on the Weatherhaven tents will be screwed shut before the camp is closed for the winter. All windows and doors on the plywood kitchen and core logging tent will be covered with plywood.

Vehicles

The ATV's snowmobiles will be stored inside one tent, or the core shed. The pick-up will be stored in Whale Cove.

Water System

The pump and hoses will be drained. All will be stored in the winterized kitchen tent for the winter.

Fuel and Chemical Storage

An inventory of fuel will be made at the end of each season and all drums will be inspected for possible leaks. The fuel will remain stored in the portable "Insta Berm" fuel berms. All empty drums will be temporarily stored at the camp before being crushed and shipped south for disposal. All empty propane cylinders will be returned to off-site facilities.

Drill additives and unused salt will be stored in the storage tent.

Waste

Combustible Waste

All combustible waste will be burned on site in an incinerator. Ash will be sealed in 45-gallon drums for transport to the Hamlet of Whale Cove's landfill.

Non-Combustible Waste

All non-combustible waste will be transferred to the Whale Cove dump for disposal. This waste will only consist of metallic materials such as cans and steel strapping and wire.

Used batteries will be transported to Ontario for disposal.

Used Motor Oil/waste fuel

Used motor oil and contaminated fuel will be sealed in 45-gallon drums and transported off site for disposal.

Grey Water Sump

Buried in a sump at the end of the season.

Sewage

The outhouse sumps will be buried at the end of the season.

Drills and Drill Sites

Prior to shutting down for the season, the drills will be secured at the final drill site of the season or returned to the camp and stored there.

All drill sites will be inspected upon completion of each hole. All combustible and metallic waste will be collected and sent to the Whale Cove dump site and all sumps will be filled. Casing will be cut off to ground level as soon as practicable after the hole collar has been surveyed. Photographs of each drill site before and after drilling will also be taken for inclusion the annual report that is sent to the NWB.

Contamination Clean Up

Any soil at camp or the drill sites that has been contaminated will be treated according to procedures outlined in the Fuel Spill Contingency Plan. The soil will be transferred off site for disposal.

Inspection and Documentation

A complete inspection of all disturbed areas at the camp and drill sites will be conducted prior to seasonal closure of the project. A full inventory of equipment will be made. Photographs will be taken of the campsite after it has been winterized.

7. Final Abandonment and Restoration

Tents and Contents

All tents and structures will be dismantled and removed, using a local contractor. All material will be taken to the Whale Cove airport or the port for final removal off site.

Equipment

All equipment including the diamond drills, pumps and generators will be removed from the project site by truck and helicopter. All material will be taken to the Whale Cove airport or the port for final removal to off site.

Fuel Cache and Chemicals

All fuel drums and chemical containers will be removed from the site. All sites that contained fuel will be inspected and any contamination will be dealt with according to the Fuel Spill Contingency Plan. Final photos of each fuel cache site will be taken.

Sumps

All sumps will be inspected and backfilled. Final photos will be taken and forwarded to the NWB.

Camp Site

A final inspection will be made. Photos will be taken and forwarded to the NWB.

Core Storage

All drill core will be removed from the site unless specified otherwise by the Nunavut government.

Drill Sites

All drill sites will be inspected upon completion of each hole. All waste will be collected and transferred to the Whale Cove municipal dump site. All sumps will be backfilled. Each drill collar will be cut off to ground level. Photographs of each site will be taken and forwarded to the NWB.

Contamination Clean Up

Any contamination will be treated according to procedures laid down in the Fuel Spill Contingency Plan. Any contamination and subsequent clean-up will be documented with photographs. All contaminated waste will be transferred off-site for disposal.

Inspection and Documentation

A complete inspection of all areas will be conducted prior to closure. Photographs will be taken for use in the final report. All appropriate agencies will be contacted upon final clean up.

8.0 Contact Numbers for Relevant Organizations

Whale Cove Hamlet Office – (867) 896-9961
Nordgold (Northquest Ltd) – (416) 306-0954
NT – NU Spill Hot Line – (867) 920-8130